

EPA Region 5 Records Ctr.



295816

7/6/92
L1190500002--Madison Co.
Clark Oil & Refining Corp.
ILD041889023
Superfund HRS

RECEIVED
JUL 6 1992

SITE ASSESSMENT SECTION



CERCLA Screening Site Inspection Report



Illinois Environmental
Protection Agency
P.O. Box 19276
Springfield, IL 62794-9276

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1. INTRODUCTION.....	1-1
2. SITE BACKGROUND	
2.1 INTRODUCTION.....	2-1
2.2 SITE DESCRIPTION.....	2-1
2.3 SITE HISTORY.....	2-6
2.4 APPLICABILITY OF OTHER STATUTES.....	2-8
3. SITE INSPECTION ACTIVITIES AND ANALYTICAL RESULTS	
3.1 INTRODUCTION.....	3-1
3.2 RECONNAISSANCE INSPECTION.....	3-1
3.3 SITE REPRESENTATIVE INTERVIEW.....	3-2
3.4 SOIL/SEDIMENT SAMPLING (DECON. PROCEDURES)...	3-3
3.5 GROUNDWATER SAMPLING (DECON. PROCEDURES)...	3-7
3.6 ANALYTICAL RESULTS.....	3-10
3.7 KEY SAMPLES.....	3-10
4. IDENTIFICATION OF SOURCES	
4.1 INTRODUCTION.....	4-1
4.2 TEL STORAGE BUILDING.....	4-1
4.3 LEADED TANKS (35-1 AND 35-2).....	4-2
4.4 TANK 10-2.....	4-2
4.5 TANK BOTTOMS PIT.....	4-3
4.6 STORMWATER RETENTION BASIN.....	4-3
4.7 FORMER TREATMENT LAGOONS.....	4-4
4.8 ILLEGAL DUMPSITE.....	4-5
5. MIGRATION PATHWAYS	
5.1 INTRODUCTION.....	5-1
5.2 GROUNDWATER PATHWAY.....	5-1
5.3 SURFACE WATER PATHWAY.....	5-3
5.4 AIR PATHWAY.....	5-5
5.5 SOIL EXPOSURE PATHWAY.....	5-5
6. BIBLIOGRAPHY.....	6-1

Appendix

A	SITE 4-MILE MAP
B	15 MILE SURFACE WATER MAP
C	CLARK FACILITY MAP
D	TARGET COMPOUND LIST
E	IEPA SITE PHOTOGRAPHS
F	AERIAL PHOTOGRAPHS
G	WELL LOGS
H	EPA FORM 2070-13

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
2-1	Site Location Map.....	2-2
2-2	Regional Area Map.....	2-3
2-3	Site Topography.....	2-4
3-1	Soil/Sediment Sampling Locations.....	3-4
3-2	Background Soil Sample.....	3-5
3-3	Groundwater Sampling Locations.....	3-9

LIST OF TABLES

<u>Table</u>		<u>Page</u>
3-1	Soil/Sediment Sampling.....	3-3
3-2	Groundwater Sampling.....	3-8
3-4	Key Sample Summary - Soils/Sediments.....	3-11
3-5	Key Sample Summary - Groundwater.....	3-12

I. INTRODUCTION

On December 11, 1990, the Illinois Environmental Protection Agency's Pre-Remedial Unit was tasked by the United States Environmental Protection Agency (U.S. EPA) to conduct a CERCLA Screening Site Inspection (SSI) of the Clark Oil and Refining Corporation/Wood River Refinery, Hartford, Illinois.

The site was initially placed on the Comprehensive Environmental Response, Compensation, and Liability Information System (CERCLIS) by the U.S. EPA in August of 1980. This action was taken as a result of the concern over possible groundwater and surface water contamination due to operations at the facility.

An initial CERCLA evaluation, in the form of a Preliminary Assessment, was completed by Kenneth L. Page of the IEPA in January of 1986. IEPA's Pre-Remedial Unit prepared an SSI workplan for Clark Oil and Refining that was approved by the U.S. EPA's Region V office in December of 1990. The sampling portion of the Screening Site Inspection was conducted on December 11 and 12, 1990 when the sampling team collected a total of six groundwater and twelve soil samples.

The purpose of a Screening Site Inspection have been stated by the U.S. EPA in a directive that states:

All sites will receive a screening SI to 1) collect

additional data beyond the PA to enable a more refined preliminary HRS (Hazard Ranking System) score, 2) establish priorities among sites most likely to qualify for the NPL (National Priorities List), and 3) identify the most critical data requirements for the listing SI step. A screening SI will not have rigorous data quality objectives (DQO's). Based on the Preliminary refined HRS score and other technical judgement factors, the site will either be designated as NFRAP (No Further Remedial Action Planned), or carried forward as an NPL listing candidate. A Listing SI will not automatically be done on these sites, however. First, they will go through a management evaluation to determine whether they can be addressed by another authority, such as RCRA [Resource Conservation and Recovery Act]... Sites that are designated NFRAP or deferred to other statutes are not candidates for a listing SI.

The listing SI will address all the data requirements of the revised HRS using field screening and NPL level DQO's. It may also provide needed data in a format to support remedial investigation workplan development. Only sites that appear to score high enough for listing and have not been deferred by another authority will receive a listing SI (U.S. EPA 1988).

U.S.EPA Region V has also instructed IEPA to identify sites during the SSI that may require removal action to remediate an immediate human health and/or environmental threat.

2. SITE BACKGROUND

2.1 Introduction

This section contains a summary of information gathered from the Preliminary Assessment, Illinois Environmental Protection Agency (IEPA) files, and discussions with site representatives.

2.2 Site Description

The Clark Oil and Refining Corporation, Wood River Refinery is located in the Village of Hartford, Madison County, Illinois (Figures 2-1, 2-2 and 2-3). The refinery operations occupy approximately 253 acres located in the following sections: Sections 34 and 35, Township 5 North, Range 9 West; and Section 3, Township 4 North, Range 9 West. Clark Oil property also includes approximately 142 acres located in Section 33, Township 5 North, Range 9 West; and Section 4, Township 4 North, Range 9 West (See map located in Appendix C for features and property boundaries). A 4-mile radius map of the area surrounding the Clark Oil facility and a 15-mile surface water map can be found in Appendices A and B respectively.

Clark Oil and Refining/Wood River Refinery is an operating petroleum refinery with an approximate plant capacity of 60,000 barrels a day. Process operations include crude desalting, atmospheric crude distillation, fluid catalytic



● SITE LOCATION

FIGURE 2-1
SITE LOCATION MAP





FIGURE 2-2

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY	SITE NAME: <u>Clark Oil & Refining Corp.</u> SITE ILD#: <u>ILD041889023</u>
REGIONAL AREA MAP	
<div data-bbox="885 1892 1279 1927"> Legend: ● Site Location </div> <div data-bbox="820 1942 1266 2011"> </div> <div data-bbox="1003 2039 1084 2066"> Scale </div>	



Source: IEPA, 1992. Base Map: U.S.G.S. Topographic Map, 1974.

Approximate Scale: 1"= 2000'

Figure 2-3

SITE TOPOGRAPHY

cracking, hydrofluoric acid alkylation, vacuum distillation, hydroprocessing, and catalytic reforming. Products include gasoline (leaded gasoline production has been discontinued), LPG (liquid propane gas), distillate fuels, and coke.

Wastewater generated in the plant passes through various unit oil traps before combining at a master trap and going to an API oil-water separator. Flow then passes through a Dissolved Air Flotation (DAF) tank before entering a single stage extended aeration/nitrification activated sludge system. Effluent is then polished in dual media filters before being discharged into the Mississippi River via IEPA NPDES (National Pollutant Discharge Elimination System) permit #IL0001244.

The following wastestreams are generated as a result of the refinery's processes: DAF Float, Slop Oil Emulsions, Heat Exchanger Bundle Cleaning Sludge, and API Separator Sludge. Heat Exchanger Bundle Cleaning Sludge is processed through the wastewater treatment system described above. DAF Float, Slop Oil Emulsions, and API Separator Sludge are piped to above ground tanks. These wastes are then piped to a coking unit where they are processed into petroleum coke, coker gasoline, coker naphtha, coke fines, and gasoline oils. All of these materials are sold as products by Clark. Two other wastes are generated during routine turnaround periods: spent catalyst and wastewater treatment sludge. These wastes are

categorized as non-hazardous. The spent catalyst is shipped to GSX-Barton (SW Permit #841332) and the waste water treatment sludge is shipped to the Peoria Disposal Company (SW Permit #941676).

An unlined lagoon serving as a stormwater retention basin is located at the intersection of Illinois Route 111 and Edwardsville Road. The basin (approximately 125,000 square feet) receives all site surface runoff and was exhibiting visual signs of hydrocarbon contamination during the October 30, 1990 reconnaissance inspection and the December 11-12, 1990 screening site inspection. An unlined pit containing crude oil tank bottoms is also present on the refinery property.

The refinery operation is bounded on the west by residential properties, on the south by agricultural and industrial property, on the east and north by industrial property (Shell Oil Refinery).

According to the IEPA Office of Chemical Safety and IEPA Technical Compliance files, a documented hydrocarbon plume is present on the groundwater in the City of Hartford and in the vicinity of Shell Oil and Clark Oil properties.

2.3 Site History

Clark Oil and Refining, Wood River Refinery began operations

in 1941 as the Wood River Refinery. The facility became part of the Sinclair Oil Corporation in July, 1950. The refinery was purchased by Clark in September of 1960, sold to APEX in September of 1983, and repurchased by Clark on November of 1989.

The facility does not currently produce leaded gasoline and all leaded gasoline has been removed. Tetraethyl lead (TEL) was the anti-knock compound used by Clark in the production of leaded gasoline. All TEL has been removed, but the bulk storage area is still present, and according to Clark representative Richard Thomas, is currently awaiting contractor removal. Waste generated by the facility containing lead was handled as Leaded Tank Bottoms, and was shipped to an unknown location for off-site disposal. The last documented shipment of Leaded Tank Bottoms was in April, 1988.

Prior to the construction of the current wastewater treatment system, all wastewater passed through various oil traps and a filter system. The effluent was then piped to a 3-stage lagoon system located just west of the levee and north of Hawthorne Street (see Appendix B). The effluent, after passing through the lagoons, was discharged to the Mississippi River.

Clark Oil property west of the levee and south of Hawthorn

Street was the site of an illegal dump according to IEPA FOS files. In 1976, an asbestos-like substance and an unidentified sludge-like material was observed at this site.

The DAF Float, Slop Oil Emulsions, and API Separator Sludge wastestreams, reused to produce petroleum coke, were pumped to Tank 10-2 for temporary storage (see facility map located in Appendix C). Tank 10-2 had been in use for approximately 48 years and had been documented by IEPA's Collinsville Field Operations Section in Collinsville personnel lacking adequate secondary containment and exhibiting visual contamination within the earthen berm surrounding the tank. Tank 10-2 underwent closure activities in June, 1989. A total of 297 tons of sludge from tank cleanout and removal and 409 tons of waste/soil from within the earthen berm were fixed and shipped by Chemical Waste Management to their Emelle, Alabama, landfill. The remaining soil inside the berm was then treated with microbes.

2.4 APPLICABILITY OF OTHER STATUTES

This section discusses the applicability of any other Environmental statutes with regards to Clark Oil and Refining.

The Clark Oil facility is considered to be a "full quantity" generator under the Resource Conservation and Recovery Act (RCRA) program according to the Federal listing of RCRA

related facilities published by the Region V offices. However, Clark Oil does not hold a permit from the IEPA. Clark filed a "Raw Materials Storage" RCRA part A permit application on November 17, 1980, which Clark then withdrew on November 23, 1982. The withdrawal of the application was approved by the U.S. EPA on December 15, 1983.

With the exception of the DAF Float, Slop Oil Emulsions, Heat Exchanger Bundle Sludge, and API Separator Sludge, products at Clark are exempt from CERCLA due to the Petroleum Exclusion. The groundwater contamination problems in the Hartford area also fall under the Petroleum Exclusion.

3. SITE INSPECTION ACTIVITIES AND ANALYTICAL RESULTS

3.1 Introduction

This section outlines procedures utilized and observations made during the CERCLA Screening Site Inspection conducted at the Clark Oil/Wood River Refinery on December 11 and 12, 1990. Specific portions of this section contain information pertaining to the reconnaissance inspection and sampling procedures. This section also details the analytical results with particular emphasis upon the Key samples.

The Screening Site Inspection for Clark Oil/Wood River Refinery was conducted in accordance with the site inspection workplan which was developed and submitted to the U.S. EPA Region V offices prior to the initiation of sampling activities.

3.2 Reconnaissance Inspection

IEPA personnel conducted a reconnaissance inspection of the Clark Oil and Refining Corporation and the surrounding area on October 30, 1990. The inspection included a walk-through of the refinery operations area and the lagoon area west of the levee to identify potential sampling locations and appropriate health and safety requirements. Mr. Richard Thomas and Mr. Joe Bean accompanied IEPA personnel on the inspection and were able to answer the questions.

Several observations were made by Agency personnel during this visit.

The refinery operations area is enclosed by a chainlink fence with full-time security personnel present at entrance points. The facility is bounded to the west by the Village of Hartford, the north and east by Shell Oil Company, the south by Shell Oil property and agricultural land.

The lagoon area west of the levee does not have restricted access, and Mr. Thomas stated that people have been seen fishing there from time to time. The southwest portion of this area is bounded by NICOR National Shipyard and lagoons, the west by the Mississippi River, the north by Shell Oil property, and the east by the levee and Illinois Rt. 3. Clark Oil also operates a barge loading pipeline transfer station at the west edge of this property on the banks of the river.

3.3 Site Representative Interview

The site representative interview was conducted on October 30, 1990, between Mr. Todd Buchanan of the IEPA and Mr. Joe Bean of Clark Oil and Refining Corporation. The meeting was arranged to explain the Pre-remedial process to the Clark representatives and to confirm the SSI schedule and objectives. During this interview Mr. Buchanan indicated that the inspection would include the collection of ten on-site and two off-site soil/sediment samples and three on-site and

three off-site groundwater samples. Mr. Thomas stated that the company wished to split samples at this time.

3.4 Soil/Sediment Sampling

A total of twelve soil/sediment samples were collected during the SSI at Clark Oil (See Figures 3-1 and 3-2 for soil/sediment sampling locations). All samples were collected using stainless steel spoons and hand augers with the soil/sediment being transferred directly to the sample jars and packed in accordance with the U.S. EPA required procedures. Table 3-1 outlines the sampling activity.

Table 3-1

Soil/Sediment Sampling

Soil/Sediment samples collected on December 11, 1990:

X101

<u>Time</u>	<u>Depth</u>	<u>Location</u>
8:45a	2-3'	N side of TEL storage building, 72.4' S of S corner post of the RR gate and 149' from corner post of site boundary fence.

X102


9:15a	1-1.5'	SE of TEL bldg., 72.8' W of foam valve and 66.6' NW of RR switch.
-------	--------	---

X104

9:55a	0-6"	Inside berm of leaded tanks 35-1 and 35-2, 26.8" SE of tank 35-2 manhole and 48.9' S of tank mixer.
-------	------	---

X105


10:20a	0-6"	NW corner of bermed area former site of tank 10-2.
--------	------	--



Source: IEPA, 1992. Base Map: U.S.G.S. Topographic Map, 1974

Approximate Scale: 1"= 1123'

Figure 3-1
SOIL/SEDIMENT SAMPLING LOCATIONS



Source: IEPA, 1992. Base Map: U.S.G.S. Topographic Map, 1974.

Approximate Scale: 1"= 2000'

Figure 3-2 BACKGROUND SOIL SAMPLE

Soil/Sediment samples taken on December 12, 1990:

X103

2:55p 0-6" Offsite roadside drainage ditch near junction of Rt. 111 and 11A, 9.8' S of SE site corner post.

X106

10:25a. 0-6" 8' from SE corner of berm, tank bottoms pit.

X107

10:50a. 3-3.5' Along west bank, 40' N of SW corner of tank bottoms pit.

X108

12:20p 1.5-2' N bank near inlet pipe of storm water retention basin. 74.5' E of NE corner of concrete skimmer base and 62.5' SW of nearby fire hydrant.

X109

12:45p 2' NW point of E bank of retention basin, 8' from bank.

X110

1:45p 2-2.5' NE corner of 1st stage lagoon near abandoned effluent discharge pipe 86' SW of SW corner of power line tower 108' W of orange gas line marker.

X111

2:20p 1' W of pond S of Hawthorn Street, site of former illegal dump, 139' SW of SW corner of power line tower.

X112

8:40a 6" Base of levee, N slope, approx. 300 yds. E of Rt. 111 near Roxana water plant.

Standard IEPA decontamination procedures were followed prior to the collection of all samples. The procedures included the scrubbing of all equipment (spoons, pans, etc.) with a non-foaming Trisodium Phosphate solution, rinsing with hot tap water, rinsing with acetone, rinsing with hot tap water

again, and final rinsed with distilled water. All equipment was air dried, then wrapped and stored in heavy-duty aluminum foil for transport to the field. Field decontamination procedures included all of the above except the hot tap water rinse.

3.5 Groundwater Sampling

Three on-site monitoring wells and three off-site public wells were sampled to determine if compounds found on the Target Compound List (TCL) have been released to groundwater (See Figure 3-2 for sampling locations). The monitor wells had 3 well volumes purged, with pH, conductivity and temperature measured. Each well was hand sampled with a Teflon bailer using nylon cord and was field filtered for total metals with a Masterflex variable speed peristaltic pump and filter stand with filters. Directly after sampling each point, preservatives were added to appropriate bottles and were packed according to U.S.EPA required procedures.

The three public wells sampled (Identified in Figure 3-2, as G501, G502, and G503) were pumped for a minimum of fifteen minutes prior to sampling with pH, conductivity, and temperature readings taken. The well samples were taken at the respective well heads prior to any treatment or filtering and were field filtered for heavy metals. The following table outlines groundwater sampling activities:

Table 3-2

Groundwater Sampling

Groundwater samples collected on December 11, 1990:

G101

<u>Time</u>	<u>Depth</u>	
11:25a	50.5'	NW part of refinery area near TEL storage building (monitor well).

G104

3:35p	100'	SE of cooling tower #2 (monitor well).
-------	------	--

G501

4:45p	107'	Hartford PW #3.
-------	------	-----------------

G502

5:05p	106'	Hartford PW #4.
-------	------	-----------------

Groundwater Samples collected on 12-12-90:


G103

11:30a	97.2'	3' E of valve tower and 4' S of cover of process well #3.
--------	-------	---

G503

8:45a	110'	Roxana PW #8.
-------	------	---------------

Standard IEPA decontamination procedures were followed prior to the collection of all samples. The procedures included the scrubbing of all equipment (bailers, buckets, etc.) with a non-foaming Trisodium Phosphate solution, rinsing with hot tap water, rinsing with acetone, rinsing with hot tap water again, and final rinsed with distilled water. All equipment was air dried, then wrapped and stored in heavy-duty aluminum foil for transport to the field. Field decontamination procedures included all of the above except the hot tap water rinse.



Source: IEPA, 1992. Base Map: U.S.G.S. Topographic Map, 1974.

Approximate Scale: 1"= 1992'

Figure 3-3

GROUNDWATER SAMPLING LOCATIONS

3.6 Analytical Results

Chemical analysis of the twelve soil/sediment samples collected during the inspection revealed the presence of the following substances: volatiles, semi-volatiles, pesticides, metals, suspected laboratory artifacts, and common inorganic soil constituents (See Figure 3-1 for sampling locations). Chemical analysis of the six groundwater samples also showed the presence of volatiles, semi-volatiles, pesticides, metals, laboratory artifacts, and common inorganic groundwater constituents (See Table 3-2 for sampling locations). Table 3-3 provides a summary of results. Complete results can be found in Volume II of this report.

3.7 Key Samples

Tables 3-4 and 3-5 identify those samples taken during the CERCLA Screening Site Inspection (SSI) which were shown to contain contaminants at levels which were significantly higher than those of background concentrations.

For a review of all contaminants detected in samples taken during the CERCLA SSI, the reader is referred to the Sample Summary Table located in the front of Volume II of this report.

Clark Oil & Refining Corp.- Key Samples
ILD 41889023

TABLE 4-1
SUMMARY

SAMPLING POINT	X101	X102	X103	X104	X105	X106	X107	X108	X109	X110	X111	X112
PARAMETER	12-11-90	12-11-90	12-12-90	12-11-90	12-11-90	12-12-90	12-12-90	12-12-90	12-12-90	12-12-90	12-12-90	12-12-90
VOLATILES	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)
Acetone	24.0	--	--	--	--	--	1300.0 J	54.0	--	--	--	14.0 U
Toluene	--	--	--	55000.0	--	--	770.0 J	--	7700.0 J	--	1500.0	7.0 U
Ethylbenzene	--	1100.0 J	--	35000.0	--	--	1100.0 J	--	--	--	1900.0	7.0 U
Xylene(total)	--	1500.0	--	--	--	--	6500.0 J	--	21000.0	--	12000.0	7.0 U
SEMIVOLATILES	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)
Naphthalene	--	--	--	450000.0	--	--	--	--	36000.0 J	--	--	1800.0 U
2-Methylnaphthalene	350.0 J	4400.0 J	--	690000.0	--	32000.0 J	--	--	160000.0	--	--	1800.0 U
Fluorene	--	--	--	5700.0	--	--	--	--	30000.0 J	--	46000.0 J	1800.0 U
Phenanthrene	--	--	--	59000.0 J	--	--	--	--	110000.0	--	220000.0	1800.0 U
Pyrene	--	--	--	9000.0	700.0 J	14000.0	--	--	100000.0	--	320000.0	1800.0 U
Benzo(a)anthracene	--	--	--	--	560.0 J	100000.0	--	--	56000.0 J	--	140000.0	1800.0 U
Chrysene	--	--	--	--	--	50000.0 J	--	--	25000.0 J	--	25000.0	1800.0 U
Acenaphthene	--	--	--	--	--	--	--	--	--	--	27000.0 J	1800.0 U
N-Nitrosodiphenylamine	--	--	--	--	--	--	--	--	40000.0 J	--	--	1800.0 U
PESTICIDES	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)	(ppb)
Heptachlor	--	--	--	190.0	--	--	--	--	--	--	--	22.0 U
Endosulfan II	--	--	--	--	252.0	1552.0	--	--	--	--	--	43.0 U
INORGANICS	(ppm)	(ppm)	(ppm)	(ppm)	(ppm)	(ppm)	(ppm)	(ppm)	(ppm)	(ppm)	(ppm)	(ppm)
Arsenic	--	--	--	46.0	--	--	--	--	--	--	--	6.5
Barium	--	--	--	--	--	533.0	--	--	--	--	--	173.0
Calcium	--	--	52700.0	56200.0	--	--	--	--	17100.0	38500.0	13000.0	4060.0
Chromium	--	--	--	--	--	--	--	--	994.0	256.0	260.0	27.5
Cobalt	--	16.1	--	--	20.2	--	--	19.2	--	--	16.8	9.2 U
Lead	--	--	--	618.0	--	--	--	167.0	--	--	163.0	43.0
Mercury	--	--	--	0.3	0.2	--	--	.48	--	--	--	.06U
Selenium	--	--	--	--	--	--	--	--	22.0	--	--	.3 U
Vanadium	--	--	--	--	--	--	--	--	150.0	--	--	33.3
Zinc	--	--	--	--	--	--	--	--	704.0	535.0	--	103.0
Cyanide	--	--	--	--	--	2.8	--	--	--	--	--	--

Clark Oil & Refining Corp.
ILD 041889023

SAMPLING POINT	G101	G503
PARAMETER	12-11-90	12-12-90
INORGANICS	(ppb)	(ppb)
Chromium	14.8	13.9 U
Sodium	69900.0	16100.0
Sulfide	14000.0	1000.0 U

4. IDENTIFICATION OF SOURCES

4.1 Introduction

In this section the author will briefly discuss the various hazardous waste sources which have been identified in the initial stages of the CERCLA site investigation.

Information concerning the size, volume, and waste composition of each source has been derived throughout the initial site assessment, reconnaissance visits, and the screening site inspection sampling action. It should be pointed out, however, that the total number and nature of each of the sources identified below may be subject to change, as the site progresses through the CERCLA site investigation program and receives further investigation.

Figure 4-1 provides a map for source location information.

4.2 TEL Storage Building

Tetra-ethyl lead was used by Clark Oil as an anti-knock compound in the production of leaded gasoline. TEL was stored from this 800 square foot building located in the northwest corner of the facility (see Appendix C). All TEL has been removed, however, the bulk storage area remains and is awaiting removal by a contractor. Storage capacity of the building is unknown. Samples taken from the north and south sides of the building contained analytically significant levels of numerous volatiles, naphthalene, and cobalt (see

Table 3-4). Pathways of concern include groundwater and soil exposure.

4.3 Leaded Tanks (35-1 and 35-2)

Leaded tanks 35-1 and 35-2 are located in the northwest corner of the facility approximately 380 feet east of the TEL storage building. The tanks are surrounded by an unlined berm, approximately 500 square feet in area. Sample results from the inspection showed analytically significant levels of numerous volatiles, semi-volatiles, Heptachlor, and metals (see Table 3-4).

4.4 Tank 10-2

Tank 10-2 had been in use for 48 years, and had stored DAF Float, Slop Oil Emulsions, and API Separator Sludge. These wastes had been pumped into Tank 10-2 from the wastewater treatment process, and were reused by Clark in the production of petroleum coke. The field operations office in Collinsville had reported that the bermed area lacked adequate secondary containment. Visible contamination within the bermed area was noted in February of 1989.

Clark stated in a letter to this Agency in March of 1989 that the tank was no longer in operation and that a complete clean-up of the tank and contaminated soil was to be completed in May, 1989.

A sample taken in the northwest corner of the bermed area showed analytically significant levels of Pyrene, Benzo(a)Anthracene, Endosulfan II, Cobalt and Mercury (see Table 3-4). Pathways of concern include: groundwater and soil exposure.

4.5 Tank Bottoms Pit

The tank bottoms pit is unlined and is located near the northeast corner of the facility and is approximately 7000 square feet in area. Analytically significant levels of volatiles, semi-volatiles, Endosulfan II, and metals (see Table 3-4) were detected in the samples.

Pathways of concern include groundwater and soil exposure.

4.6 Stormwater Retention Basin

The stormwater retention basin is located at the eastern boundary of the facility and occupies an area of approximately 125,000 square feet. The unlined basin catches runoff from the facility. Visual signs of hydrocarbon contamination were apparent during the reconnaissance inspection conducted on October 30, 1990.

Analytically significant levels of acetone and metals were detected in the sample taken from the north bank of the retention basin near the inlet pipe. High levels of volatiles, semi-volatiles, and metals were detected in the sample taken at the northwest point of the east bank of the

basin (see Table 3-4).

Pathways of concern include: groundwater and soil exposure pathway (workers on-site), and the surface water pathway for the environmental threat (the Illinois Department of Conservation's National Wetland Inventory maps have designated this area, as well as several others at this site as wetlands).

4.7 Former Treatment Lagoons

Clark Oil used three lagoons located west of the levee and south of Hawthorne Street for treatment of wastewater prior to the construction of the current treatment facility. The lagoons received effluent from Clark's oil traps and filter system. Effluent was then discharged to the Mississippi River from these lagoons. Volume of these lagoons is unknown, and is dependent upon the level of the river.

Analytically significant levels of metals were detected in the sample taken from the northeast corner of the first stage lagoon near an abandoned effluent discharge pipe (see Table 3-4).

Pathways of concern is groundwater, and surface water-including the environmental threat that these metals may pose, and also drinking water due to the number of intakes located downstream from these lagoons. The threat to the human food chain is also a potential threat.

4.8 Illegal Dumpsite

Located west of the lagoon system, this area was used by Clark for demolition debris, however, an unknown sludge was reported present by the Collinsville field office on December 14, 1978. Clark Oil was informed by the Agency that they were in violation of Agency regulations.

Analytically significant levels of volatiles, semi-volatiles, and metals were detected in samples collected in December of 1990.

Pathways of concern include: groundwater and surface water.

5.0 MIGRATION PATHWAYS

5.1 Introduction

This section discusses data and information that apply to potential migration pathways and targets of TCL compounds that can be attributed to Clark Oil and Refining Corporation. The pathways of concern are groundwater, surface water, and soil exposure (direct contact). The air migration pathway is also noted.

5.2 Groundwater Pathway

The Groundwater Migration Pathway is of concern at this site due to the potential for the contaminants that have been released during spills and leaks to the soil to find their way into the groundwater system.

Geologic and hydrogeologic information was made available through Illinois State Water Survey (ISWS) well logs, Illinois State Geological Survey reports, and IEPA files.

Clark Oil and Refining Corporation/Wood River Refinery, is located in the Mississippi River Valley of the East St. Louis area commonly referred to as the "American Bottoms". Water-yielding deposits of the area are permeable sands and gravels in unconsolidated valley fill. In the vicinity of the site, the upper 20 to 30 feet consists of silts and clays with discontinuous sand lenses present in some areas, with

materials coarsening with depth. The most favorable water-yielding deposits usually occur at depths of 60 to 90 feet. Studies of the aquifer suggest a hydraulic conductivity of 2,000 gallons/day from a saturated thickness of 75 to 100 feet.

The aquifer of concern consists of the entire unconsolidated alluvial deposits overlaying the limestone bedrock of the area.

The direction of groundwater flow in the refinery operations area is to the southeast. Flow in this area is artificially influenced by industrial well withdrawals, with lesser cones of depression located within the regional flow regime. Flow direction in the lagoon areas to the west of the levee is to the east, also artificially induced by pumpage with some recharge expected from the Mississippi River.

There are four public water supply systems utilizing the aquifer of concern within a four mile radius of the site (see Appendix A for public well locations). The Village of Hartford has four municipal wells serving 1,900 people, five Wood River wells supply 12,446 people, three Roxana wells serve 3,873 people and seven Bethalto well serve 22,783 residents. Located less than four miles from the site is East Alton's well field serving 7096 people. The five above mentioned municipalities distribution systems are all

interconnected and with the addition of the few area residents using private wells brings the total population potentially affected by groundwater to approximately 62,424. A listing of the number of public wells and approximate number of private wells and users in each distance category are identified below.

<u>Distance</u>	<u>Wells</u>	<u>Private Well Population</u>	<u>Total Population</u>
0-1/4 mile	0	0	0
1/4-1/2 mile	0	0	0
1/2-1 mile	9	8	1918
1-2 miles	21	50	1308
2-3 miles	165	595	40,034
3-4 miles	130	316	20,422

5.3 Surface Water

Clark Oil and Refining's property west of the levee and Hartford is situated in the 30-year floodplain of the Mississippi River between the Mississippi River mile 196 and 198. According to the St. Louis District of the Army Corps of Engineers, the highest river stage on record occurred in April of 1973. During this time the lagoons became a part of the river as the stage crested at 431.3 feet. The predicted 30-year, 100-year, and 500-year flood events would reach a maximum elevation at river mile 197 of 434 feet, 436.8 feet, and 441.5 feet respectively.

Two surface water intakes are located downstream of Clark Oil. Illinois-American Water Company has an intake 4.5 miles downriver near Mississippi River mile 192. The St. Louis intake is located north of river mile 190, 6.2 miles downriver (see Appendix B). Collectively, these intakes supply millions of people with water.

Pool 27 of the Mississippi River is used extensively for fishing and recreational purposes according to the Illinois State Atlas.

The illegal dump and the former treatment lagoons are sources that could contribute to contaminants entering the surface water pathway. Of concern in this pathway are the drinking water intakes that are located downstream, most notably, those used by the City of St. Louis.

The Environmental threat is also of concern at this source. According to maps by the U.S. Department of the Interior, this lagoon area, located west of the levee, is a noted wetland area. And, as was noted previously, Clark representatives have stated that people have been seen fishing in the lagoon area.

According to maps received from the Illinois Department of Conservation, National Wetlands Inventory, there are also designated wetland areas in the storm water retention ponds,

as well as several other areas within the operations area.

5.4 Air Releases to the air were observed during the SSI while collecting soil/sediment and groundwater samples. Upwind and downwind air samples of the facility failed to document an observed release. A photo-ionization detector (HNU) with an 11.7 eV lamp was used to screen the soil/sediment samples and groundwater samples and monitor for any air releases.

Approximately 34,000 people live within four miles of Clark Oil and Refining.

The following table provides information concerning populations located within a 4-mile radius of the Clark Oil facility.

<u>Distance</u>	<u>Population</u>
On a source	0
Greater than 0-1/4 mile	0
Greater than 1/4-1/2 mile	40
Greater than 1/2-1 mile	3817
Greater than 1-2 miles	10398
Greater than 2-3 miles	10359
Greater than 3-4 miles	13817

5.5 Soil Exposure

The soil exposure threat to the approximately 500 Clark workers within the operations area of the facility at Clark.

However, direct exposure by the public is not of concern in

the operations area of the facility due to the area being fenced and the security guards located at the entrance. The lagoon areas west of the levee, however, do not have access control and Clark Oil representatives stated that people have been seen fishing in the lagoons on Clark property.

Approximately 2,000 people live within one mile of the lagoon area west of the levee.

6. BIBLIOGRAPHY

- Gary, James H. and Handwerk, Glenn E. Petroleum Refining: Technology and Economics. Marcel Dekker, Inc., New York, New York, 1984.
- Illinois Department of Conservation, National Wetlands Inventory Map, 1988, Wood River 7.5 Minute Quadrangle.
- Illinois Environmental Protection Agency, 1986, Potential Hazardous Waste Site Assessment for Clark Oil & Refining Corporation ILD041889023, prepared by Kenneth L. Page, Springfield, Illinois.
- Illinois Environmental Protection Agency, Bureau of Land, file for Clark Oil & Refining Corporation, L1190500002.
- Illinois Environmental Protection Agency, Bureau of Water, file for Clark Oil & Refining Corporation.
- U.S. Environmental Protection Agency, Resource Conservation and Recovery Act (RCRA) status list, March 25, 1992.
- U.S. Census Bureau, 1990, Average persons per household in Madison County, Illinois.
- USGS, 1974, Wood River, IL. Quadrangle, 7.5 Minute Series.
- USGS, 1974, Bethalto, IL. Quadrangle, 7.5 Minute Series.

SDMS US EPA Region V

Imagery Insert Form

Some images in this document may be illegible or unavailable in SDMS.
Please see reason(s) indicated below:

Illegible due to bad source documents. Image(s) in SDMS is equivalent to hard copy.

Specify Type of Document(s) / Comments:

Includes ___ COLOR or RESOLUTION variations.

Unless otherwise noted, these pages are available in monochrome. The source document page(s) is more legible than the images. The original document is available for viewing at the Superfund Records Center.

Specify Type of Document(s) / Comments:

Confidential Business Information (CBI).

This document contains highly sensitive information. Due to confidentiality, materials with such information are not available in SDMS. You may contact the EPA Superfund Records Manager if you wish to view this document.

Specify Type of Document(s) / Comments:

x

Unscannable Material:

Oversized ___x___ or ___ Format.

Due to certain scanning equipment capability limitations, the document page(s) is not available in SDMS.

Specify Type of Document(s) / Comments:


APPENDIX A – SITE 4-MILE MAP; APPENDIX B - 15-MILE SURFACE WATER MAP

Document is available at the EPA Region 5 Records Center.

Specify Type of Document(s) / Comments:

APPENDIX A

APPENDIX B



Source: IEPA, 1990. Base Map: U.S. Department of the Interior National Wetlands Inventory Map, 1987.

Scale: 1:24000

SDMS US EPA Region V

Imagery Insert Form

Document ID:

295816

Some images in this document may be illegible or unavailable in SDMS.

Please see reason(s) indicated below:



Illegible due to bad source documents. Image(s) in SDMS is equivalent to hard copy.

Specify Type of Document(s) / Comments:

--



Includes ____ COLOR or ____ RESOLUTION variations.

Unless otherwise noted, these pages are available in monochrome. The source document page(s) is more legible than the images. The original document is available for viewing at the Superfund Records Center.

Specify Type of Document(s) / Comments:

--



Confidential Business Information (CBI).

This document contains highly sensitive information. Due to confidentiality, materials with such information are not available in SDMS. You may contact the EPA Superfund Records Manager if you wish to view this document.

Specify Type of Document(s) / Comments:

--



Unscannable Material:

Oversized X or ____ Format.

Due to certain scanning equipment capability limitations, the document page(s) is not available in SDMS. The original document is available for viewing at the Superfund Records center.

Specify Type of Document(s) / Comments:

APPENDIX C - PLOT PLAN REFINERY REDUCED



Document is available at the EPA Region 5 Records Center.

Specify Type of Document(s) / Comments:

--

APPENDIX C

APPENDIX D

TARGET COMPOUND LIST

Volatile Target Compounds

Chloromethane	1,2-Dichloropropane
Bromomethane	cis-1,3-Dichloropropene
Vinyl Chloride	Trichloroethene
Chloroethane	Dibromochloromethane
Methylene Chloride	1,1,2-Trichloroethane
Acetone	Benzene
Carbon Disulfide	trans-1,3-Dichloropropene
1,1-Dichloroethene	Bromoform
1,1-Dichloroethane	4-Methyl-2-pentanone
1,2-Dichloroethene (total)	2-Hexanone
Chloroform	Tetrachloroethene
1,2-Dichloroethane	1,1,2,2-Tetrachloroethane
2-Butanone	Toluene
1,1,1-Trichloroethane	Chlorobenzene
Carbon Tetrachloride	Ethylbenzene
Vinyl Acetate	Styrene
Bromodichloromethane	Xylenes (total)

Base/Neutral Target Compounds

Hexachloroethane	2,4-Dinitrotoluene
bis(2-Chloroethyl) Ether	Diethylphthalate
Benzyl Alcohol	N-Nitrosodiphenylamine
bis(2-Chloroisopropyl) Ether	Hexachlorobenzene
N-Nitroso-Di-n-Propylamine	Phenanthrene
Nitrobenzene	4-Bromophenyl-phenylether
Hexachlorobutadiene	Anthracene
2-Methylnaphthalene	Di-n-Butylphthalate
1,2,4-Trichlorobenzene	Fluoranthene
Isophorone	Pyrene
Naphthalene	Butylbenzylphthalate
4-Chloroaniline	bis(2-Ethylhexyl) Phthalate
bis(2-chloroethoxy) Methane	Chrysene
Hexachlorocyclopentadiene	Benzo(a) Anthracene
2-Chloronaphthalene	3,3'-Dichlorobenzidene
2-Nitroaniline	Di-n-Octyl Phthalate
Acenaphthylene	Benzo(b) Fluoranthene
3-Nitroaniline	Benzo(k) Fluoranthene
Acenaphthene	Benzo(a) Pyrene
Dibenzofuran	Indeno(1,2,3-cd) Pyrene
Dimethyl Phthalate	Dibenz(a,h) Anthracene
2,6-Dinitrotoluene	Benzo(g,h,i) Perylene
Fluorene	1,2-Dichlorobenzene
4-Nitroaniline	1,3-Dichlorobenzene
4-Chlorophenyl-phenylether	1,4-Dichlorobenzene

Acid Target Compounds

Benzoic Acid	2,4,6-Trichlorophenol
Phenol	2,4,5-Trichlorophenol
2-Chlorophenol	4-Chloro-3-methylphenol
2-Nitrophenol	2,4-Dinitrophenol
2-Methylphenol	2-Methyl-4,6-dinitrophenol
2,4-Dimethylphenol	Pentachlorophenol
4-Methylphenol	4-Nitrophenol
2,4-Dichlorophenol	


Pesticide/PCB Target Compounds

alpha-BHC	Endrin Ketone
beta-BHC	Endosulfan Sulfate
delta-BHC	Methoxychlor
gamma-BHC (Lindane)	alpha-Chlorodane
Heptachlor	gamma-Chlorodane
Aldrin	Toxaphene
Heptachlor epoxide	Aroclor-1016
Endosulfan I	Aroclor-1221
4,4'-DDE	Aroclor-1232
Dieldrin	Aroclor-1242
Endrin	Aroclor-1248
4,4'-DDD	Aroclor-1254
Endosulfan II	Aroclor-1260
4,4'-DDT	

Inorganic Target Compounds

Aluminum	Manganese
Antimony	Mercury
Arsenic	Nickel
Barium	Potassium
Beryllium	Selenium
Cadmium	Silver
Calcium	Sodium
Chromium	Thallium
Cobalt	Vanadium
Copper	Zinc
Iron	Cyanide
Lead	Sulfide
Magnesium	Sulfate



APPENDIX E



Source: IEPA, 1992. Base Map: USGS Topographic Map, 1974

Scale 1:24000

REFERENCE FOR PHOTOGRAPH LOCATION MAP



Photograph Location Map

DATE: December 11, 1990

TIME: 8:45 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 1

LOCATION: L0312340008

Clark Oil and Refining Corp.

ILD041880238

PICTURE TAKEN TOWARD: E

COMMENTS: Photo taken at
sample X101 at the north side
of TEL storage building.



DATE: December 11, 1990

TIME: 8:45 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 2

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: W

COMMENTS: Photo taken at
sample X101 at the northside
of TEL storage building.



DATE: December 11, 1990

TIME: 9:15 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 3

LOCATION: L0312300082

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: NW

COMMENTS: Photo taken at
sample X102. Note TEL storage
area in the background.



DATE: December 11, 1990

TIME: 9:15p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 4

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: NW

COMMENTS: Photo taken at
sample X102.



DATE: December 11, 1990

TIME: 9:55 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 5

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: SE

COMMENTS: Photo taken at
sample X104 inside berm of
leaded gasoline storage tanks



DATE: December 11, 1990

TIME: 9:55 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 6


LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: N

COMMENTS: Photo taken at
sample X104.



DATE: December 11, 1990

TIME: 9:15 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 15

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: E

COMMENTS: Photo taken at

sample X103 outside Clark

perimeter fence in ditch

near intersection of Rts 111

& 114.



TKB

DATE: December 12, 1990

TIME: 2:55 p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 16

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: W

COMMENTS: Photo taken at

X103.



TKB

DATE: December 12, 1990

TIME: 10:25 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 17

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: NW

COMMENTS: Photo taken at
sample X106- tank bottoms pit



DATE: December 12, 1990

TIME: 10:25 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 18

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: NW

COMMENTS: Photo taken at
sample X106.



DATE: December 12, 1990

TIME: 10:50 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 19

LOCATION: L0312340008

Clark Oil and Refining Corp.

ILD041880238

PICTURE TAKEN TOWARD: N

COMMENTS: Photo taken at
sample X107. Photo of tank
bottoms pit.



DATE: December 12, 1990

TIME: 10:50 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 20

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: NE

COMMENTS: Photo taken at
sample X107.



DATE: December 12, 1990

TIME: 12:20 p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 21

LOCATION: L0312300082

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: E

COMMENTS: Photo taken at
sample X108. Photo taken at
storm water retention basin.



DATE: December 12, 1990

TIME: 12:20 p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 22

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: E

COMMENTS: Photo taken at
sample X108.



DATE: December 11, 1990

TIME: 10:20 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 7


LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: S

COMMENTS: Photo taken at
sample X105 inside berm of
former site of Tank 10-2.



DATE: December 11, 1990

TIME: 10:20 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 8


LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: E

COMMENTS: Photo taken at
sample X105.



DATE: December 12, 1990

TIME: 12:45 p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 23

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: W

COMMENTS: Photo taken at
sample X109. Sample taken
at storm water retention
basin.



DATE: December 12, 1990

TIME: 12:45 p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 24

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: N

COMMENTS: Photo taken at
X109.



DATE: December 12, 1990

TIME: 1:45 p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 25

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: W

COMMENTS: Photo taken at
sample X110 near inlet pipe
of abandoned lagoon #1 west
of levee.



DATE: December 12, 1990

TIME: 1:45 p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 26

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: NE

COMMENTS: Photo taken at
sample X110.



DATE: December 12, 1990

TIME: 2:20 p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 27

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: E

COMMENTS: Photo taken at
sample X111 in area of
alleged dump site west of
levee.



DATE: December 12, 1990

TIME: 2:20 p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 28

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: _____

COMMENTS: Photo taken at
sample X111.



DATE: December 12, 1990

TIME: 8:40 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 29

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: N

COMMENTS: Photo taken at
sample X112 (background).



DATE: December 12, 1990

TIME: 8:40 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 30

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: N

COMMENTS: Photo taken at
sample X112.



DATE: December 11, 1990

TIME: 11:25 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: _____


LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: _____

COMMENTS: Sample G101, photo
not available.



DATE: December 11. 1990

TIME: 11:25 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: _____


LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: _____

COMMENTS: Sample G101, photo
not available.



DATE: December 12. 1990

TIME: 11:30 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 31

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: N

COMMENTS: Photo taken at
G103- well located inside
concrete casement to right
of date board.



DATE: December 12. 1990

TIME: 11:30 a.m.

PHOTOGRAPH TAKEN BY:

Ken Corkill

PHOTOGRAPH NUMBER: 32

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: S

COMMENTS: Photo taken at
sample G103.



DATE: December 11, 1990

TIME: 3:35 p.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 9

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: W

COMMENTS: Photo taken at
sample G104.



DATE: December 11, 1990

TIME: 8:40 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 10


LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: E

COMMENTS: Photo taken at
sample G104.



DATE: December 11, 1990

TIME: 4:45 p.m.

PHOTOGRAPH TAKEN BY:

Ken Corkill

PHOTOGRAPH NUMBER: 11


LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: N

COMMENTS: Photo taken at
sample G501- Hartford PW #3.



DATE: December 11, 1990

TIME: 4:45 p.m.

PHOTOGRAPH TAKEN BY:

Ken Corkill

PHOTOGRAPH NUMBER: 12


LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: S

COMMENTS: Photo taken at
sample G501.



DATE: December 11, 1990

TIME: 5:05 p.m.

PHOTOGRAPH TAKEN BY:

Ken Corkill

PHOTOGRAPH NUMBER: 13


LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: N

COMMENTS: Photo taken at
sample G502- Hartford PW #4.



DATE: December 11, 1990

TIME: 5:05 p.m.

PHOTOGRAPH TAKEN BY:

Ken Corkill

PHOTOGRAPH NUMBER: 14

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: S

COMMENTS: Photo taken at
sample G502.



DATE: December 12, 1990

TIME: 8:45 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 33

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023

PICTURE TAKEN TOWARD: W

COMMENTS: Photo taken at
sample G503 - Roxana PW #8 -
well located in pumphouse.

DATE: December 12, 1990

TIME: 8:45 a.m.

PHOTOGRAPH TAKEN BY:

Todd Buchanan

PHOTOGRAPH NUMBER: 34

LOCATION: L0312340008

Clark Oil & Refining Corp.

ILD041889023


PICTURE TAKEN TOWARD: N

COMMENTS: Photo taken at
sample G503.



APPENDIX F

N



I.D.O.T. - 1980

Scale: 1" = 808'


N ↑



I.D.O.T. - 1988

Scale: 1"=881'

N →



I.D.O.T. - 1981

Scale: 1"=429'

APPENDIX G

Sample of water collected from ~~KK~~ farm residence of Louis L. Hoehn on State Route 67 approx 2 miles south of Hartford.

City South of Hartford County Madison

Section 9.26 Twp. No. 4 N. Range 9 W.
Approx. 700 feet West and 800 feet North of the
Location (in feet from section corner) S.E. corner of Section 9, T.4 N., R.9 W.

Owner Louis L Hoehn Authority Louis L Hoehn

Contractor A.J. Bienemann Address South Roxana, Illinois

Date drilled 1947 Elev. above sea level top of well 424 + MSL. et hunk

Depth 85 feet below basement floor. This well is a 4-inch driven well in the basement of the farm residence of Mr. Hoehn. It is equipped with a deep well pump and pumps to a pressure tank. Water is used for domestic use. Sample was collected from a hydrant in yard and temperature was not recorded.

Were drill cuttings saved No Where filed _____

Size hole 4-inch If reduced, where and how much No

Casing record 4-inch drive pipe.

Cannot measure water level in this well but water level in 40 ft well

Distance to water when not pumping _____ Distance to water in
in yard was at elevation 401.76 when this sample was collected.
feet after pumping at _____ G. P. M. for _____ hours

Reference point for above measurements _____

Type of pump _____ Distance to cylinder _____

Length of cylinder _____ Length of suction pipe below cylinder _____

Length stroke _____ Speed _____

Hours used per day _____ Type of power _____

Rating of motor _____ Rating of pump in G. P. M. _____

Can following be measured: (1) Static water level No

(2) Pumping level No (3) Discharge No

(4) Influence on other wells _____

Temperature of water Not Recorded Was water sample collected yes

Date November 10, 1952 Effect of water on meters, hot water coils, etc. _____

Date of Analysis _____ Analysis No. 130410 SS

Please send copy of analysis to

Mr. Louis L. Hoehn
Rt 1, Esat Alton, Illinois

Recorder _____

Date _____
cc to Jones

MAD4N9W-9.26

November 18, 1952

PARTIAL MINERAL ANALYSIS

Sample of water collected November 10, 1952 from well at farm residence of Louis L. Hoehn on State Route 67, approx. 2 miles South of Hartford, Illinois in Madison County. Location of well: approx. 700' W. and 800' N. of the SE Corner of Section 9, T. 4 N., R. 9 W. Depth: 85 feet below basement floor.

LABORATORY NO. 130,410

		ppm.	epm.			ppm.	epm.
Iron (total)	Fe	2.0		Chloride	Cl	8.	.23
				Sulfate	SO ₄	113.1	2.35
				Alkalinity (as CaCO ₃)		308.	6.16
Turbidity		5		Hardness (as CaCO ₃)		420.	8.40
Color		0		Residue		472.	
Odor		0					

ppm. = parts per million
epm. = equivalents per million
ppm. x .0583 = grains per gallon

STATE WATER SURVEY DIVISION

R. M. King, Asst. Chemist

RMK:it

W Copy -
 Dept. of Public Health
 Yellow Copy - Well Contractor
 Blue Copy - Well Owner

INSTRUC TO DRILLERS

FILL IN ALL PERTINENT INFORMATION. REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 616, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS, 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH
 WELL CONSTRUCTION REPORT

1. Type of Well

- a. Dug ____ Bored ____ Hole Diam. ____ in. Depth ____ ft.
 Curb material ____ Buried Slab: Yes ____ No ____
 b. Driven X Drive Pipe Diam. 2 in. Depth 41 ft.
 c. Drilled ____ Finished in Drift ____ In Rock ____
 Tubular ____ Gravel Packed ____
 d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

2. Distance to Nearest:

Building 7' 6" Ft. Seepage Tile Field 150'
 Cess Pool ____ Sewer (non Cast iron) ____
 Privy ____ Sewer (Cast iron) ____
 Septic Tank ____ Barnyard ____
 Leaching Pit ____ Manure Pile ____

3. Is water from this well to be used for human consumption?

Yes X No ____

4. Date well completed 2-4-78

5. Permanent Pump Installed? Yes X No ____
 Manufacturer MYERS HCM 150 Type JET
 Capacity 20 gpm. Depth of setting 31 ft.

6. Well Top Sealed? Yes X No ____

7. Pitless Adaptor Installed? Yes X No ____

8. Well Disinfected? Yes X No ____

9. Water Sample Submitted? Yes ____ No X

REMARKS:

IDPH 4.065
 10/68

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner GARY AIKEN Well No. 1
 Address SOUTH ROXANA, ILL. R#6 Edwardsville
 Driller JAMES J. BIENEMANN License No. 102-124
 11. Permit No. 66400 Date 9-7-77
 12. Water from XX SAND Formation 122e
 at depth 17 to 40 ft. Sec. 122e
 14. Screen: Diam. 2 in. Twp. 4N
 Length: 5 ft. Slot 10 Rge. 9W
 Elev. 429

15. Casing and Liner Pipe

Diam. (In.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>2"</u>	<u>SCH. 40 galv steel</u>	<u>0</u>	<u>40</u>

SHOW
 LOCATION IN
 SECTION PLAT
100'W SE 1E

16. Size Hole below casing: ____ in.
 17. Static level 18 ft. below casing top which is 1 ft.
 above ground level. Pumping level ____ ft. when pumping at ____
 gpm for ____ hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>TOPSOIL</u>	<u>10</u>	<u>10</u>
<u>SANDS FINE TO MEDIUM</u>	<u>30</u>	<u>40</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED James J. Bienemann DATE 2-4-78

White Copy -
Ill. Dept. of Public Health
Yellow Copy - Well Contractor
Blue Copy - Well Owner

INSTRUCTIONS TO WELLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 616, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS, 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

Madison County

ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

1. Type of Well

- a. Dug ☐ Bored ☒ Hole Diam. 32 in. Depth 107 ft.
Curb material ☐ Buried Slab: Yes ☐ No ☐
b. Driven ☐ Drive Pipe Diam. ☐ in. Depth ☐ ft.
c. Drilled ☒ Finished in Drift ☒ In Rock ☐
Tubular ☐ Gravel Packed ☒
d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

2. Distance to Nearest:

Building 70 Ft. Seepage Tile Field ☐
Cess Pool ☐ Sewer (non Cast iron) ☐
Privy ☐ Sewer (Cast iron) ☐
Septic Tank ☐ Barnyard ☐
Leaching Pit ☐ Manure Pile ☐

3. Is water from this well to be used for human consumption?

Yes ☐ No ☒

4. Date well completed Nov 18 1974

5. Permanent Pump Installed? Yes ☒ No ☐

Manufacturer ☐ Type Turbine
Capacity 500 gpm. Depth of setting 80' ft.

6. Well Top Sealed? Yes ☒ No ☐

7. Pitless Adaptor Installed? Yes ☐ No ☒

8. Well Disinfected? Yes ☐ No ☒

9. Water Sample Submitted? Yes ☐ No ☒

REMARKS:

Irrigation well

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Charles Losch Well No. 2
Address R1 EAST ALTON ILL
Driller E. Linker License No. 102-86
11. Permit No. 34803 Date 11-13-1974
12. Water from Sand + gravel 13. County Madison
at depth 65 to 107 ft. Sec. 12.4
14. Screen: Diam. 16 in. Twp. 4N
Length: 3/16 ft. Slot 3/16 Rge. 9W
Elev.

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>16"</u>	<u>Steel</u>	<u>-1.5</u>	<u>74.2</u>
<u>16"</u>	<u>Steel (Screen)</u>	<u>74.2</u>	<u>106.85</u>

SHOW LOCATION IN SECTION PLAT
1000' S, 2000' W,
107' NE

16. Size Hole below casing: in.
17. Static level 19 ft. below casing top which is 1.5 ft. above ground level. Pumping level 24 ft. when pumping at 400 gpm for 1 hours. App.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>Clay and sand</u>	<u>5</u>	<u>5</u>
<u>fine sand</u>	<u>50</u>	<u>55</u>
<u>Gray med sand</u>	<u>5</u>	<u>60</u>
<u>Gray med-coarse sand</u>	<u>15</u>	<u>75</u>
<u>med fine tan sand</u>	<u>5</u>	<u>80</u>
<u>Gray med coarse sand</u>	<u>5</u>	<u>85</u>
<u>Gray very coarse sand</u>	<u>5</u>	<u>90</u>
<u>Tan med-coarse sand</u>	<u>5</u>	<u>95</u>
<u>Gray Coarse sand</u>	<u>12</u>	<u>107</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED

Eugene Linker

DATE

6-9-'78

APPENDIX H



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION

01 STATE IL 02 SITE NUMBER 041889023

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) Clark Oil & Refining Corporation 02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER Hawthorne Street
03 CITY Hartford, 04 STATE IL 05 ZIP CODE 02048 06 COUNTY Madison 07 COUNTY CODE 119 08 CONG DIST 21
09 COORDINATES LATITUDE 38.5025.0 LONGITUDE 090.2459.0 10 TYPE OF OWNERSHIP (Check one) ☒ A. PRIVATE ☐ B. FEDERAL ☐ C. STATE ☐ D. COUNTY ☐ E. MUNICIPAL ☐ F. OTHER ☐ G. UNKNOWN

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 12.11.90 02 SITE STATUS ☒ ACTIVE ☐ INACTIVE 03 YEARS OF OPERATION 1941 Present UNKNOWN
MONTH DAY YEAR BEGINNING YEAR ENDING YEAR

04 AGENCY PERFORMING INSPECTION (Check all that apply)

☒ A. EPA ☐ B. EPA CONTRACTOR ☐ C. MUNICIPAL ☐ D. MUNICIPAL CONTRACTOR ☐ E. STATE ☐ F. STATE CONTRACTOR ☐ G. OTHER
(Name of firm) (Name of firm) (Specify)


05 CHIEF INSPECTOR	06 TITLE	07 ORGANIZATION	08 TELEPHONE NO.
<u>Todd Buchanan</u>	<u>Environmental Prot. Spec.</u>	<u>IEPA</u>	<u>671</u>
09 OTHER INSPECTORS	10 TITLE	11 ORGANIZATION	12 TELEPHONE NO.
<u>Greg Dunn</u>	<u>ERS</u>	<u>IEPA</u>	<u>(217) 782-6760</u>
<u>Ken Corkill</u>	<u>ERS</u>	<u>IEPA</u>	<u>(217) 782-6760</u>
<u>Tim Murphy</u>	<u>ERS</u>	<u>IEPA</u>	<u>(217) 782-6760</u>
			()
			()

13 SITE REPRESENTATIVES INTERVIEWED	14 TITLE	15 ADDRESS	16 TELEPHONE NO.
<u>Richard Thomas</u>		<u>Clark Oil, Hawthorne Street</u>	()
<u>Joe Bean</u>		<u>Clark Oil, Hawthorne Street</u>	()
			()
			()
			()
			()

17 ACCESS GAINED BY (Check one) ☒ PERMISSION ☐ WARRANT 18 TIME OF INSPECTION 8:00 AM 19 WEATHER CONDITIONS Sunny, cold -40°F.

IV. INFORMATION AVAILABLE FROM

01 CONTACT	02 OF (Agency/Organization)	03 TELEPHONE NO.		
<u>Thomas Crause</u>	<u>Illinois EPA / RPMS</u>	<u>(217) 782-6760</u>		
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM	05 AGENCY	06 ORGANIZATION	07 TELEPHONE NO.	08 DATE
<u>Kimberlee Nika</u>	<u>IEPA</u>	<u>RPMS</u>	<u>217/782-6760</u>	<u>6.23.92</u> MONTH DAY YEAR



01 PHYSICAL STATES (Check all that apply)	02 WASTE QUANTITY AT SITE (Measure of waste quantities must be identifiable)	03 WASTE CHARACTERISTICS (Check all that apply)
<input checked="" type="checkbox"/> A. SOLID <input checked="" type="checkbox"/> B. POWDER, FINES <input checked="" type="checkbox"/> C. SLUDGE <input type="checkbox"/> D. OTHER _____ (Specify)	<input type="checkbox"/> E. SLURRY <input checked="" type="checkbox"/> F. LIQUID <input type="checkbox"/> G. GAS TONS _____ CUBIC YARDS <u>Unknown</u> NO. OF DRUMS _____	<input checked="" type="checkbox"/> A. TOXIC <input type="checkbox"/> B. CORROSIVE <input checked="" type="checkbox"/> C. RADIOACTIVE <input checked="" type="checkbox"/> D. PERSISTENT <input type="checkbox"/> E. SOLUBLE <input type="checkbox"/> F. INFECTIOUS <input checked="" type="checkbox"/> G. FLAMMABLE <input checked="" type="checkbox"/> H. IGNITABLE <input type="checkbox"/> I. HIGHLY VOLATILE <input type="checkbox"/> J. EXPLOSIVE <input checked="" type="checkbox"/> K. REACTIVE <input type="checkbox"/> L. INCOMPATIBLE <input type="checkbox"/> M. NOT APPLICABLE

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE	UNKNOWN	—	K050, K051, K048
OLW	OILY WASTE	UNKNOWN	—	K049, K048
SOL	SOLVENTS			
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS	UNKNOWN	—	K052

[illegible]

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS	N/A		FDS		
FDS			FDS		
FDS			FDS		

Illinois EPA/ Division of Land Files
Division of Air Files
Division of Water Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE IL 02 SITE NUMBER 04889023

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: ~46,000 04 NARRATIVE DESCRIPTION

Samples taken at monitoring wells indicated the presence of metals, (groundwater) drinking wells could be affected.

01 ☒ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: ~1,000,000 04 NARRATIVE DESCRIPTION

Population of the City of St. Louis derives drinking water from intakes located 7mi. downstream of site. Human Food Chain - Fishing.

01 ☒ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: ~38,431 04 NARRATIVE DESCRIPTION

Release of SO₂ emissions exceeded limitations, according to available information, also - spent catalyst released, caused health concerns.

01 ☒ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Several incidents of fires related to groundwater contamination in the area - these incidents caused (potentially) by leaking transfer pipes underground.

01 ☒ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

Workers at operations area have the potential to be affected due to contaminants buried in top 2' of soil. Also - area west of levee - due to accessibility. People have been seen fishing.

01 ☒ F. CONTAMINATION OF SOIL 02 ☒ OBSERVED (DATE: 12/1/90) ☐ POTENTIAL ☐ ALLEGED
03 AREA POTENTIALLY AFFECTED: 220 (Acres) 04 NARRATIVE DESCRIPTION

Samples of soil & sediment indicated significantly elevated levels of contaminants present in soil/sediment.

01 ☒ G. DRINKING WATER CONTAMINATION 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: ~1,000,000 04 NARRATIVE DESCRIPTION

Drinking water wells in 4-mile radius as well as City of St. Louis intakes.

01 ☒ H. WORKER EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 WORKERS POTENTIALLY AFFECTED: 300 04 NARRATIVE DESCRIPTION

Direct contact & volatile compounds present.

01 ☒ I. POPULATION EXPOSURE/INJURY 02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
03 POPULATION POTENTIALLY AFFECTED: _____ 04 NARRATIVE DESCRIPTION

General public does not have access to operations area, however, area west of levee is accessible.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE IL 02 SITE NUMBER 041889023

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☒ J. DAMAGE TO FLORA
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

Samples taken west of levee indicate contaminants present.

01 ☒ K. DAMAGE TO FAUNA
04 NARRATIVE DESCRIPTION (include name(s) of species)

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

Same as above

01 ☒ L. CONTAMINATION OF FOOD CHAIN
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☒ POTENTIAL

☐ ALLEGED

Same as above. Area is in 30-year floodplain. People seen fishing.

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES
(Spills/Runoff/Standing liquids, Leaking drums)

02 ☒ OBSERVED (DATE: 12/10/90)

☐ POTENTIAL

☒ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: _____

04 NARRATIVE DESCRIPTION

Spills from tanks have occurred. Unlined berms prevalent.

01 ☒ N. DAMAGE TO OFFSITE PROPERTY
04 NARRATIVE DESCRIPTION

02 ☒ OBSERVED (DATE: 1/988)

☐ POTENTIAL

☐ ALLEGED

A spill in late 1980's spilled onto private property, damaging grass.

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: _____)

☐ POTENTIAL

☐ ALLEGED

01 ☒ P. ILLEGAL/UNAUTHORIZED DUMPING
04 NARRATIVE DESCRIPTION

02 ☒ OBSERVED (DATE: 1976)

☐ POTENTIAL

☐ ALLEGED

Clark Oil cited for illegal dumpsite west of levee.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: _____

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e. g., state files, sample analysis, reports)

Illinois EPA / Bureau of Land files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION
01 STATE IL 02 SITE NUMBER 041809023

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input checked="" type="checkbox"/> A. NPDES	<u>IL0001244</u>	<u>—</u>	<u>—</u>	
<input type="checkbox"/> B. UIC				
<input checked="" type="checkbox"/> C. AIR	<u>119050APP</u>			
<input type="checkbox"/> D. RCRA				
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCC PLAN				
<input type="checkbox"/> G. STATE (Specify)				
<input type="checkbox"/> H. LOCAL (Specify)				
<input type="checkbox"/> I. OTHER (Specify)				
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input checked="" type="checkbox"/> A. SURFACE IMPOUNDMENT	<u>UNKNOWN</u>	<u>—</u>	<input type="checkbox"/> A. INCINERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input checked="" type="checkbox"/> B. PILES	<u>UNKNOWN</u>	<u>—</u>	<input type="checkbox"/> B. UNDERGROUND INJECTION	
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input checked="" type="checkbox"/> D. TANK, ABOVE GROUND	<u>UNKNOWN</u>	<u>—</u>	<input checked="" type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	
<input checked="" type="checkbox"/> H. OPEN DUMP	<u>UNKNOWN</u>	<u>—</u>	<input type="checkbox"/> H. OTHER (Specify)	
<input type="checkbox"/> I. OTHER (Specify)				

06 AREA OF SITE
2200 (Acres)
TOTAL

07 COMMENTS

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)
☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☒ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

Berms surrounding loaded bottom tanks, Tank 10-2, Stormwater retention pond, all are unlined.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☐ YES ☒ NO

02 COMMENTS

Operations area is fenced+guarded, however, area west of levee is accessible.

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)

IEPA/Bureau of Land files.



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE IL 02 SITE NUMBER 041889023

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY
(Check as applicable)

SURFACE WELL
COMMUNITY A. ☒ B. ☒
NON-COMMUNITY C. ☒ D. ☒

02 STATUS

ENDANGERED AFFECTED MONITORED
A. ☐ B. ☐ C. ☐
D. ☐ E. ☐ F. ☐

03 DISTANCE TO SITE

A. 17 Surface to intake
B. 1 (mi) public

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☒ A. ONLY SOURCE FOR DRINKING ☐ B. DRINKING
(Other sources available) ☐ C. COMMERCIAL, INDUSTRIAL, IRRIGATION ☐ D. NOT USED, UNUSEABLE
(Limited other sources available)
COMMERCIAL, INDUSTRIAL, IRRIGATION
(No other water sources available)

02 POPULATION SERVED BY GROUND WATER

03 DISTANCE TO NEAREST DRINKING WATER WELL 1 (mi)

04 DEPTH TO GROUNDWATER

1 (ft)

05 DIRECTION OF GROUNDWATER FLOW

Unknown

06 DEPTH TO AQUIFER
OF CONCERN

260 (ft)

07 POTENTIAL YIELD
OF AQUIFER

Unknown (gpd)

08 SOLE SOURCE AQUIFER

☒ YES ☐ NO

09 DESCRIPTION OF WELLS (including useage, depth, and location relative to population and buildings)

Hartford #4 - 1900 pop.
Bevalto - #7 - 221783
E. Alton - -7096

Roxana #3 - 3873
Wood River - #5 - 12,446
Private - 969 pop.

10 RECHARGE AREA

☐ YES
☐ NO

COMMENTS

11 DISCHARGE AREA

☐ YES
☐ NO

COMMENTS

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☒ A. RESERVOIR, RECREATION
DRINKING WATER SOURCE ☐ B. IRRIGATION, ECONOMICALLY
IMPORTANT RESOURCES ☐ C. COMMERCIAL, INDUSTRIAL ☐ D. NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME:

Mississippi River

AFFECTED

DISTANCE TO SITE

1/4 (mi)
1/4 (mi)
1/4 (mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN

ONE (1) MILE OF SITE

A. NO. OF PERSONS

TWO (2) MILES OF SITE

B. NO. OF PERSONS

THREE (3) MILES OF SITE

C. NO. OF PERSONS

02 DISTANCE TO NEAREST POPULATION

1/12 (mi)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE

04 DISTANCE TO NEAREST OFF-SITE BUILDING

200' (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)

Onsite - 0
0-1/4 mile - 0
1/4-1/2 mi - 40
1/2-1 mi - 3817
1-2 mi - 10398

2-3 mi - 10359
3-4 mi - 13817



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 041889023

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A. $10^{-8} - 10^{-6}$ cm/sec ☐ B. $10^{-4} - 10^{-6}$ cm/sec ☒ C. $10^{-4} - 10^{-3}$ cm/sec ☐ D. GREATER THAN 10^{-3} cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A. IMPERMEABLE
(Less than 10^{-6} cm/sec) ☐ B. RELATIVELY IMPERMEABLE
($10^{-4} - 10^{-6}$ cm/sec) ☒ C. RELATIVELY PERMEABLE
($10^{-2} - 10^{-4}$ cm/sec) ☐ D. VERY PERMEABLE
(Greater than 10^{-2} cm/sec)

03 DEPTH TO BEDROCK

200 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

unknown (ft)

05 SOIL pH

06 NET PRECIPITATION

3 (in)

07 ONE YEAR 24 HOUR RAINFALL

(in)

08 SLOPE
SITE SLOPE

%

DIRECTION OF SITE SLOPE

TERRAIN AVERAGE SLOPE

%

09 FLOOD POTENTIAL

SITE IS IN 30 YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

wetlands located on-site

OTHER

A. (mi)

B. (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

(mi)

ENDANGERED SPECIES:

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS/NATIONAL/STATE PARKS,
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS
PRIME AG LAND AG LAND

A. (mi)

B. 400 ft (mi)

C. (mi)

D. 1/4 (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

Site is located in an area of oil refineries (to the north, east & south) and is bordered by a residential area to the west. Agricultural land is also located to the south.

Area west of levee - located west of populations, topography is flat - in floodplain & wetlands area.

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

Illinois EPA/Bureau of Land Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE FL 02 SITE NUMBER 04188903

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER	<u>5</u>	<u>IEPA Labs - Spfld + Champaign</u>	<u>—</u>
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL / <u>Sediment</u>	<u>12</u>	<u>IEPA Labs - Spfld + Champaign</u>	<u>—</u>
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS
<u>Water</u>	<u>pH, conductivity, temperature</u>

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input checked="" type="checkbox"/> AERIAL	02 IN CUSTODY OF <u>IEPA-Land</u> <small>(Name of organization or individual)</small>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS <u>IEPA-Land</u>

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA/Bureau of Land Files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 041889023

II. CURRENT OWNER(S)				PARENT COMPANY (If applicable)			
01 NAME Clark Oil & Refining Corp.		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) Hawthorne Street		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY Hartford		06 STATE IL	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	12 CITY		13 STATE	14 ZIP CODE
III. PREVIOUS OWNER(S) (List most recent first)				IV. REALTY OWNER(S) (If applicable; list most recent first)			
01 NAME HPEX		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME Clark Oil		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) Same as above		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
01 NAME Sinclair Oil Corp.		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	05 CITY		06 STATE	07 ZIP CODE
V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)							
EPA/Bureau of Land files							



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

II. CURRENT OPERATOR (Provide if different from owner)					OPERATOR'S PARENT COMPANY (If applicable)				
01 NAME			02 D+B NUMBER		10 NAME			11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)			13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE		14 CITY		15 STATE	16 ZIP CODE	
08 YEARS OF OPERATION		09 NAME OF OWNER							
III. PREVIOUS OPERATOR(S) (List most recent first; provide only if different from owner)					PREVIOUS OPERATORS' PARENT COMPANIES (If applicable)				
01 NAME			02 D+B NUMBER		10 NAME			11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)			13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE		14 CITY		15 STATE	16 ZIP CODE	
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD							
01 NAME			02 D+B NUMBER		10 NAME			11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)			13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE		14 CITY		15 STATE	16 ZIP CODE	
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD							
01 NAME			02 D+B NUMBER		10 NAME			11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)			13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE		14 CITY		15 STATE	16 ZIP CODE	
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD							
IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)									



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE IL 02 SITE NUMBER 041889023

II. PAST RESPONSE ACTIVITIES

01 <input type="checkbox"/> A. WATER SUPPLY CLOSED 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> B. TEMPORARY WATER SUPPLY PROVIDED 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> C. PERMANENT WATER SUPPLY PROVIDED 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> D. SPILLED MATERIAL REMOVED 04 DESCRIPTION <u>TANK 10-2</u>	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> E. CONTAMINATED SOIL REMOVED 04 DESCRIPTION _____	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> F. WASTE REPACKAGED 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> G. WASTE DISPOSED ELSEWHERE 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> H. ON SITE BURIAL 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> I. IN SITU CHEMICAL TREATMENT 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> J. IN SITU BIOLOGICAL TREATMENT 04 DESCRIPTION <u>TANK 10-2</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> K. IN SITU PHYSICAL TREATMENT 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> L. ENCAPSULATION 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> M. EMERGENCY WASTE TREATMENT 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> N. CUTOFF WALLS 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> O. EMERGENCY DIKING/SURFACE WATER DIVERSION 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> P. CUTOFF TRENCHES/SUMP 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> Q. SUBSURFACE CUTOFF WALL 04 DESCRIPTION <u>NA</u>	02 DATE _____	03 AGENCY _____



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 041889023

II. ON-SITE GENERATOR

01 NAME Clark Oil	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.) Hawthorne Street	04 SIC CODE
05 CITY Dartford	06 STATE 07 ZIP CODE IL 122048

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA/ Bureau of Landfiles



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER
IL 041889023

II PAST RESPONSE ACTIVITIES (Continued)

01 <input type="checkbox"/> R. BARRIER WALLS CONSTRUCTED 04 DESCRIPTION NA	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> S. CAPPING/COVERING 04 DESCRIPTION NA	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> T. BULK TANKAGE REPAIRED 04 DESCRIPTION NA	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> U. GROUT CURTAIN CONSTRUCTED 04 DESCRIPTION NA	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> V. BOTTOM SEALED 04 DESCRIPTION NA	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> W. GAS CONTROL 04 DESCRIPTION NA	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> X. FIRE CONTROL 04 DESCRIPTION NA	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> Y. LEACHATE TREATMENT 04 DESCRIPTION NA	02 DATE _____	03 AGENCY _____
01 <input checked="" type="checkbox"/> Z. AREA EVACUATED 04 DESCRIPTION Air release -	02 DATE 12/91	03 AGENCY _____
01 <input type="checkbox"/> 1. ACCESS TO SITE RESTRICTED 04 DESCRIPTION Fence & gate	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> 2. POPULATION RELOCATED 04 DESCRIPTION	02 DATE _____	03 AGENCY _____
01 <input type="checkbox"/> 3. OTHER REMEDIAL ACTIVITIES 04 DESCRIPTION	02 DATE _____	03 AGENCY _____

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

1 EPA Bureau of Land files



POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☐ YES ☐ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

1. Type of Well

- a. Dug . Bored . Hole Diam. in. Depth ft.
Curb material . Buried Slab: Yes No
- b. Driven X. Drive Pipe Diam. 2 in. Depth 65 ft.
- c. Drilled . Finished in Drift . In Rock .
Tubular . Gravel Packed .
- d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)
CLAY	0	29

2. Distance to Nearest:

Building 30 Ft. Seepage Tile Field 85
Cess Pool Sewer (non Cast iron) ABOVE GROUND
Privy Sewer (Cast iron) 60
Septic Tank 75 Barnyard
Leaching Pit Manure Pile

3. Is water from this well to be used for human consumption?

Yes X No

4. Date well completed 12-24-79

5. Permanent Pump Installed? Yes X No
Manufacturer BURKS THNAD Type P.W. JET
Capacity 15 gpm. Depth of setting 58 ft.

6. Well Top Sealed? Yes X No

7. Pitless Adaptor Installed? Yes No X

8. Well Disinfected? Yes X No

9. Water Sample Submitted? Yes No X

REMARKS: PUMP INSTALLED ABOVE GROUND
IN SMALL PUMP HOUSE.

GEOLOGICAL WATER SURVEYS WATER WELL RECORD

10. Dept. Mines and Minerals permit No. 91522 Year 1979
11. Property owner JAMES J. BIENEMANN Well No. 1
Address RR#1 BOX 629AA EAST ALTON, ILL 62024
Driller JAMES J. BIENEMANN License No. 102-124
12. Water from SAND Formation 13. County PIEPERSON
at depth 29 to 65 ft. Sec. 12.7h
14. Screen: Diam. 2 in. Twp. 4N
Length: 5 ft. Slot 10 Rng. 9W
Elev. 440

X		

15. Casing and Liner Pipe

Diam. (In.)	Kind and Weight	From (Ft.)	To (Ft.)
2	5-H 40 A-53 GALV	0	60
2	53 SUPER WGT. 10 S&W	60	65

SHOW LOCATION IN SECTION PLAT
142'S 190'W
NE/C NW NW.

16. Size Hole below casing: in.

17. Static level 29.5 ft. below casing top which is .5 ft. above ground level. Pumping level ft. when pumping at gpm for hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
TOP SOIL 10 FT	10 FT	10'
SAND - FINE - MEDIUM	55'	65'
CLAY BAND APPROX 23 FT		
TEST PUMPED APPROX 2 HRS @ 35+ GPM		
(CONTINUE ON SEPARATE SHEET IF NECESSARY)		

SIGNED James J. Bienemann DATE 1-4-80

White Copy -
Ill. Dept. of Public Health
Yellow Copy - Well Contractor
Blue Copy - Well Owner

INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE
DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST
JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER
SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

1. Type of Well

- a. Dug ☐ Bored ☐ Hole Diam. 16 in. Depth 102 ft.
Curb material ☐ Buried Slab: Yes ☐ No ☐
b. Driven ☐ Drive Pipe Diam. ☐ in. Depth ☐ ft.
c. Drilled ☒ Finished in Drift ☒ In Rock ☐
Tubular ☐ Gravel Packed ☐
d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)
bentonite & natural	grade	81

2. Distance to Nearest:

- Building ☒ Ft. Seepage Tile Field ☒
Cess Pool ☒ Sewer (non Cast iron) ☒
Privy ☒ Sewer (Cast iron) ☒
Septic Tank ☒ Barnyard ☒
Leaching Pit ☒ Manure Pile ☒

3. Well furnishes water for human consumption? Yes ☐ No ☒

4. Date well completed August 25, 1987

5. Permanent Pump Installed? Yes ☐ Date ☐ No ☒

- Manufacturer ☐ Type ☐ Location ☐
Capacity ☐ gpm. Depth of Setting ☐ Ft.

6. Well Top Sealed? Yes ☒ No ☐ Type PVC cap

7. Pitless Adapter Installed? Yes ☐ No ☐

- Manufacturer ☐ Model Number ☐
How attached to casing? ☐

8. Well Disinfected? Yes ☒ No ☐

9. Pump and Equipment Disinfected? Yes ☐ No ☐

10. Pressure Tank Size ☐ gal. Type ☐

- Location ☐

11. Water Sample Submitted? Yes ☐ No ☒

REMARKS:

Co # 25050

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Fred & Pam Heepke Well No. ☐

Address RR # 1, Edwardsville, Il.

Driller Clarence Kohnen License No. 102-30

11. Permit No. 134354 Date August 13, 1987

12. Water from Gray Sand & Gravel 13. County Madison

at depth 18 to 108 ft. Sec. 12.7e

14. Screen: Diam. 16 in. Twp. 4 N

Length: 21 ft. Slot 1st 11 ft. #40 Rge. 9 W

last 10 ft. #50 Elev. x

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
16"	PVC sch 40	0 + 1	81
16"	Stainless Steel screen	81	102

SHOW
LOCATION IN
SECTION PLAT
150'S4, 150'E4

*SW NW.
Irrigation*

16. Size Hole below casing: ☐ in.

17. Static level ☐ ft. below casing top which is ☐ ft.

above ground level. Pumping level ☐ ft. when pumping at ☐
gpm for ☐ hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Brown Clay	1	1
Brown Sand	1	2
Brown Clay	4	6
Black Sandy Clay	6	12
Brown Sandy Clay	6	18
Brown Sand & Gravel Course to fine w/ small sheets of gray clay	15	33
Brown Sand & Gravel clean fine to course	10	43
Gray Clay & Fine Gray Sand Dirty	6	49

cont. on back

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Clarence Kohnen DATE 12-1-87
CB

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

GEOLOGICAL AND WATER SURVEYS WELL RECORD

1.. Type of Well

- a. Dug ☐ Bored ☒ Hole Diam. 30 in. Depth 39 ft.
Curb material ☐ Buried Slab: Yes ☐ No ☐
- b. Driven ☐ Drive Pipe Diam. ☐ in. Depth ☐ ft.
- c. Drilled ☐ Finished in Drift ☐ In Rock ☐
Tubular ☐ Gravel Packed ☒
- d. Grout: ☐

(KIND)	FROM (F1)	TO (F1)

2. Distance to Nearest:

Building 507 Fl. _____
 Cess Pool _____
 Privy _____
 Septic Tank 1007 _____
 Leaching Pit _____

Seepage Tile Field _____
 Sewer (non Cast iron) _____
 Sewer (Cast iron) _____
 Barnyard _____
 Manure Pile _____

3. Well furnishes water for human consumption? Yes ☒ No ☐
4. Date well completed _____
5. Permanent Pump Installed? Yes _____ Date _____ No ☒
Manufacturer _____ Type _____ Location _____
Capacity _____ gpm. Depth of Setting _____ Ft.
6. Well Top Sealed? Yes ☒ No _____ Type _____
7. Pitless Adapter Installed? Yes _____ No ☒
Manufacturer _____ Model Number _____
How attached to casing? _____
8. Well Disinfected? Yes ☒ No _____
9. Pump and Equipment Disinfected? Yes _____ No _____
10. Pressure Tank Size _____ gal. Type _____
Location _____
11. Water Sample Submitted? Yes _____ No ☒

REMARKS:

10. Property owner Fred Vogel Well No. _____
Address Edmundsville ILL
Driller GARY E. NALL License No. 92-623
11. Permit No. 111214 Date _____
12. Water from clay 13. County Madison
Formation
at depth _____ to _____ ft. Sec. 144d
14. Screen: Diam. _____ in. Twp. 4N
Length: _____ ft. Slot _____ Rge. 9W
Elev. _____
- | | | |
|--|--|---|
| | | |
| | | |
| | | |
| | | 8 |

A 4x4 grid with a small figure in the center. The figure is a stick figure with its arms raised, standing on a small circle. It is located in the second column from the left and the second row from the bottom.

15. Casing and Liner Pipe

Dim. (In.)	Kind and Weight	From (Ft.)	To (Ft.)
30	Concrete	30	

SHOW
LOCATION IN
SECTION PLAT
NW NW SE

16. Size Hole below casing: _____ in.
17. Static level _____ ft. below casing top which is _____ ft. above ground level. Pumping level _____ ft. when pumping at _____ gpm for _____ hours.

18.	FORMATIONS PASSED, THROUGH	THICKNESS	DEPTH OF BOTTOM
	clay	29	

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Greg E. Noll DATE 5-22-84

White Copy -
Ill. Dept. of Public Health
Yellow Copy - Well Contractor
Blue Copy - Well Owner

INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 616, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS, 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

1. Type of Well

- a. Dug ☐ Bored ☐ Hole Diam. in. Depth ft.
Curb material Buried Slab: Yes ☐ No ☐
- b. Driven ☒ Drive Pipe Diam. 2 in. Depth 40 ft.
- c. Drilled ☐ Finished in Drift ☐ In Rock ☐
Tubular ☐ Gravel Packed ☐
- d. Grout: ☐

(KIND)	FROM (Ft.)	TO (Ft.)
Drilled clay around surface casing	0	10 FT

2. Distance to Nearest:

Building 50 Ft. Seepage Tile Field ☐
Cess Pool ☐ Sewer (non Cast iron) ☐
Privy ☐ Sewer (Cast iron) ☐
Septic Tank ☐ Barnyard 50
Leaching Pit ☐ Manure Pile ☐

3. Is water from this well to be used for human consumption?

Yes ☐ No ☒

4. Date well completed 3-9-70

5. Permanent Pump Installed? Yes ☒ No ☐
Manufacturer Red Jack 1 hp Co Type Hand force Pump
Capacity gpm. Depth of setting ft.

6. Well Top Sealed? Yes ☒ No ☐

7. Pitless Adaptor Installed? Yes ☐ No ☒

8. Well Disinfected? Yes ☒ No ☐

9. Water Sample Submitted? Yes ☐ No ☒

REMARKS:

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Arthur East Well No.

Address Wesley Lane South Roxana, Ill

Driller James J. Brunemann License No. 92-152

11. Permit No. RF 17441 Date 11-14-69

12. Water from Hand 13. County Madison

Formation Hand

at depth 19 to 40 ft. Sec. 12.8h

14. Screen: Diam. 2 in. Twp. 4N

Length: 5 ft. Slot 10 Rge. 4W

Elev.

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>2" 10</u>	<u>Hand 40 Pipe</u>	<u>0</u>	<u>40</u>
<u>6" 16</u>	<u>Surface Casing</u>	<u>0</u>	<u>10</u>
<u>6" 16</u>	<u>Casing Pipe</u>	<u>0</u>	<u>10</u>

SHOW
LOCATION IN
SECTION PLAT

65'S 330'E NW/4

16. Size Hole below casing: ☒ in.

17. Static level 20 ft. below casing top which is 1 ft.
above ground level. Pumping level 1 ft. when pumping at 1 gpm for 1 hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>Sandy loam Topsoil E. of</u>	<u>8</u>	<u>8</u>
<u>Fine to Medium Sand w/ clay streaks</u>	<u>32</u>	<u>40</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED James J. Brunemann DATE 3-15-70

White Copy -
Ill. Dept. of Public Health
Yellow Copy - Well Contractor
Blue Copy - Well Owner

INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE
DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST
JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER
SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

1. Type of Well

- a. Dug ____ Bored ____ Hole Diam. ____ in. Depth ____ ft.
Curb material ____ Buried Slab: Yes ____ No ____
- b. Driven X Drive Pipe Diam. X in. Depth ____ ft.
- c. Drilled ____ Finished in Drift ____ In Rock ____
Tubular ____ Gravel Packed ____
- d. Grout:

(KIND)	FROM (FT.)	TO (FT.)

2. Distance to Nearest:

Building 30 Ft. Seepage Tile Field OK

Cess Pool OK Sewer (non Cast iron) OK

Privy OK Sewer (Cast iron) OK

Septic Tank OK Barnyard OK

Leaching Pit OK Manure Pile OK

3. Well furnishes water for human consumption? Yes X No ____

4. Date well completed Nov. 13, 1980

5. Permanent Pump Installed? Yes X Date ____ No ____

Manufacturer Webtrol Type Sub. Location well

Capacity 15 gpm. Depth of Setting 40' Ft.

6. Well Top Sealed? Yes X No ____ Type ____

7. Pitless Adapter Installed? Yes X No ____

Manufacturer Monitor Model Number Snappy

How attached to casing? Clamp

8. Well Disinfected? Yes ____ No X

9. Pump and Equipment Disinfected? Yes ____ No X

10. Pressure Tank Size 2 gal. Type ____

Location to be installed by the customer

11. Water Sample Submitted? Yes ____ No X

REMARKS:

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Charles N. Stavely Well No. # 1

Address R. R. # 1, Box # 659, East Alton, Ill.

Driller Earl C. Baker Jr. License No. 92-62

11. Permit No. 92253 Date 11-7-80

12. Water from Sand 13. County Madison

at depth 90.2' to 93.7' ft. Sec. 15.5a

14. Screen: Diam. 5.5 in. Twp. 4 N

Length: 5.4 ft. Slot 20 Rge. 9 W

Elev. ____

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>6" I.D.</u>	<u>Blk. Steel Pipe</u>	<u>+ 1.5</u>	
	<u>#19, .280</u>		
	<u>Sch. 40</u>		<u>90.2'</u>

SHOW
LOCATION IN
SECTION PLAT
150' N. & 2500'
E. of SW Cor.
of Sec.

16. Size Hole below casing: ____ in.

17. Static level 19.78 ft. below casing top which is 1.5' ft.
above ground level. Pumping level 21.5 ft. when pumping at 15
gpm for 20 hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Clay	10'	10'
Dirty Sand	10'	20'
Sand (Packed with Dirty Strips)	50'	70'
Clean Sand	23.7'	93.7'

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED A.L. And D.K. Baker DATE 11-13-80

White Copy -
Ill. Dept. of Public Health
Yellow Copy - Well Contractor
Blue Copy - Well Owner

INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 616, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS, 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

1. Type of Well

- a. Dug ☐ Bored ☒ Hole Diam. 36 in. Depth 40 ft.
Curb material ☐ Buried Slab: Yes ☐ No ☒
- b. Driven ☐ Drive Pipe Diam. ☐ in. Depth ☐ ft.
- c. Drilled ☐ Finished in Drift ☒ In Rock ☐
Tubular ☐ Gravel Packed ☐
- d. Grout:

(KIND)	FROM (FT.)	TO (FT.)
CONCRETE	- 40	+ 1

2. Distance to Nearest:

Building 60 Ft. Seepage Tile Field 150
Cess Pool ☐ Sewer (non Cast iron) ☐
Privy ☐ Sewer (Cast iron) ☐
Septic Tank 150 Barnyard ☐
Leaching Pit ☐ Manure Pile ☐

3. Is water from this well to be used for human consumption?

Yes ☒ No ☐

4. Date well completed JUNE 1975

5. Permanent Pump Installed? Yes ☒ No ☐
Manufacturer RED JACKET Type SLIP
Capacity 10 gpm. Depth of setting 38 ft.

6. Well Top Sealed? Yes ☒ No ☐

7. Pitless Adaptor Installed? Yes ☐ No ☒

8. Well Disinfected? Yes ☒ No ☐


9. Water Sample Submitted? Yes ☐ No ☐

REMARKS:

IDPH 4.065
10/68

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner CURT FLETCHER Well No.
Address RR 3 HARTFORD ILL
Driller HENRY L BUSH License No. 92-376
11. Permit No. 38634 Date 3-16-76
12. Water from SANDY-CLAY Formation 13. County MAADISON
at depth 30 to 40 ft. Sec. 16.30
14. Screen: Diam. in. Twp. 4N
Length: ft. Slot Rge. 9W
Elev.



15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
36	CONCRETE	- 40	+ 1

SHOW
LOCATION IN
SECTION PLAT
SE NW SE

16. Size Hole below casing: in.
17. Static level 25 ft. below casing top which is 1 ft.
above ground level. Pumping level ft. when pumping at
gpm for hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
TOP SOIL	1	1
BLACK CLAY	3	4
SANDY YELLOW CLAY	26	30
CLAY-SAND-GRAVEL	30	40

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Henry L Bush DATE 3-16-76

White Copy -
Ill. Dept. of Public Health
Yellow Copy - Well Contractor
Blue Copy - Well Owner

INSTRUCTIONS TO DRILL

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE
DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST
JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER
SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

GEOLOGICAL AND WATER SURVEYS WELL RECORD

1. Type of Well

- a. Dug Bored X Hole Diam. 36 in. Depth 40 ft.
Curb material Buried Slob: Yes No X
b. Driven Drive Pipe Diam. in. Depth ft.
c. Drilled Finished in Drift X In Rock
Tubular Gravel Packed
d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)
CONCRETE	-10	GRADE

2. Distance to Nearest:

Building 70 Ft. Seepage Tile Field
Cess Pool NONE Sewer (non Cast iron) N
Privy NONE Sewer (Cast iron) U
Septic Tank NONE Barnyard N
Leaching Pit Manure Pile E

3. Well furnishes water for human consumption? Yes X No

4. Date well completed JUNE 1975

5. Permanent Pump Installed? Yes X Date JULY No

Manufacturer RED-TACK Type SUBM Location
Capacity 10 gpm. Depth of Setting 38 Ft.

6. Well Top Sealed? Yes X No Type CAPPING

7. Pitless Adapter Installed? Yes No X

Manufacturer Model Number

How attached to casing?

8. Well Disinfected? Yes X No

9. Pump and Equipment Disinfected? Yes X No

10. Pressure Tank Size 0 gal. Type HYDRUCELL

Location BURIED

11. Water Sample Submitted? Yes No X

REMARKS:

10. Property owner WILLIAM MORTLAND Well No.

Address HARTFORD ILL

Driller HENRY BUSH License No. 92-375

11. Permit No. 38641 Date 3-22-76

12. Water from SAND 13. County MADISON

at depth 34 to 36 ft. Sec. 16.20

14. Screen: Diam. in. Twp. 4N

Length: ft. Slot Rge. 9W

Elev.

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
36	CONCRETE	-40	+1

SHOW
LOCATION IN
SECTION PLAT
SE NLU SE

16. Size Hole below casing: in.

17. Static level 22 ft. below casing top which is 1 ft.

above ground level. Pumping level ft. when pumping at gpm for hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
TOP SOIL	3	3
YELLOW CLAY	8	11
BLUE DRIFT	23	34
BLUE SAND	2	36
DRIFT	4	40

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Henry J Bush DATE 3-22-76

APPENDIX H
HARTFORD PWS ANALYSIS